



**HINDMARSH**

Leadership at work

# BIM and Collaboration Get Results

TEMC

1<sup>st</sup> Sept 2015

# Company History Hindmarsh

## National Diversified Builder / Developer

Institutional – teaching, research, public buildings

Health – research, clinical, health centers, hospitals

Residential – private developers, institutions, development

Experienced in various delivery models:

- Lump Sum
- Managing Contractor with designers novated
- Design and Construct

Construction

Development

Retirement

Capital

# Hindmarsh Projects



# Construction context

## Construction in Australia

10% of GDP

\$150 Billion Industry - University sector is a large component

Not without its CHALLENGES

- Low productivity
- High cost
- Lack of skills and knowledge
- Adversarial culture

# Property Council – Case Study

## “Projects as Wealth creators – Drivers of Project Excellence”

- Many projects fail to satisfy their clients and end-users
- Only 1 in 10 projects is considered an excellent project, which is defined by:
  - Satisfied end-users
  - Happy client (achieving investment goals)
  - Happy contractors and consultants (achieving margins)
  - Project participants enjoyed experience
  - Community appreciation (Good aesthetic/environmental project outcome)
- **Excellent project delivery was achieved by removing wasted effort and creating a positive and equitable project environment**

# BIM – Hindmarsh experience

**BIM has been a powerful tool for Hindmarsh to assist in creating better projects for all involved parties**

## **Benefits:**

- Improved collaboration between project stakeholders
- Optimised design coordination
- Reduced construction costs (through risk mitigation)
- Improved programme performance
- Improved quality (design and construction)
- Reduced waste (design, management, physical)
- Continuous improvement for all involved (on the job learning)
- Enhanced performance of the building
- FM capable models available at the end of the journey

# BIM – Hindmarsh Experience

## BIM – Hindmarsh South Australia

3D Modeling of complex façade and structural steel	2005
Uni of Adelaide – New Engineering Building – plantroom services	2008
Mawson Lakes School – Architectural, Structure and services	2009
Flinders Ctr Innovation in Cancer – Architectural, Structure, Services	2009
South Australia Health and Medical Research Institute	2010
University of SA – Jeffrey Smart Building	2012
Ergo Apartments	2014


Used in various delivery models:

- Lump Sum
- Managing Contractor with designers separate
- Managing Contractor with designers novated
- Design and Construct

# BIM – Hindmarsh Experience

## BIM – Uni of Adelaide New Engineering Building

LOD 500 Virtual Prototype





# BIM - SAHMRI

## SAHMRI

Managing Contractor

Complex everything

- Cyclotron
- Animal facilities
- Laboratories
- Containment Suites
- Complex structure
- Complex façade
- Staged site possession
- Staged fitout



# BIM - SAHMRI





## SAHMRI – BIM Process

- Design team committed to BIM 1 yr into the project (Revit & Navisworks)
- HCA used models for 4D initiatives – planning around staging and programming
- HCA engaged VICO for lower levels coordination – focus on services
- VICO process included an ‘embedded’ staff member on HCA team.
- Output was a design audit which allowed for resolution of issues prior to construction.
- Services trades developed the model to LOD400, used for setout, prefabrication and as-built submission


ID	C-006	Trades Involved	ME	Severity	High
<b>Description</b>	Multiple clashes between 18"x4" cable tray and 8"x8" supply duct. The cable tray was routed close above to the ceiling (elev. 10'-0"), but neither the clearance or the clash cannot be avoided. The duct cannot be raised, because the steel joists are too close to the ceiling. There is not enough space for these elements.				
<b>Floor</b>	1st floor	<b>Grid Reference</b>	T-V/4.4.6	<b>Sheet Reference</b>	MH-111A; Cable Tray Layouts (1 of 4); A-611A
<b>Modeling Assumption</b>	The clash was modeled, the ceiling elevation needs to be lowered.				

# BIM - SAHMRI

## Design Development



## Design Development



# BIM - SAHMRI



# BIM - SAHMRI



# BIM – UniSA Jeffrey Smart Building

## Jeffrey Smart Building

### Collaboration with:

- Client – UniSA
- Consultants – John Wardle Architects & Phillips Pilkington Architects
- Bestec (Services)
- Wallbridge & Gilbert (Structural)



Design was 2D in CAD through to For Construction

Hindmarsh proposed BIM to UniSA

# BIM – UniSA Jeffrey Smart Building

## Jeffrey Smart Building

### Stage 1 BIM Design Stage




- Built the 3D model and produced Constructability Report – thousands of design discrepancies identified.
- Missing information, clashes and discrepancies between disciplines all resolved in collaborative workshops with design team.
- For Construction documentation update
- Model issued to services trades





# BIM – UniSA Jeffrey Smart Building

## Constructability report example - CLASH

ID	C-006	Trades Involved	ME	Severity	High
Description	Multiple clashes between 18"x4" cable tray and 8"x8" supply duct. The cable tray was routed close above to the ceiling (elv. 10'-0"), but neither the clearance or the clash cannot be avoided. The duct cannot be raised, because the steel joists are too close to the ceiling. There is not enough space for these elements.				
Floor	1st floor	Grid Reference	T-V/4-4.6	Sheet Reference	MH-111A; Cable Tray Layouts (1 of 4); A-611A
Modeling Assumption	   <p>The clash was modeled, the ceiling elevation needs to be lowered.</p>				

# BIM – UniSA Jeffrey Smart Building

## Constructability report example – missing / inconsistent dimensions

HINDMARSH

VICO SOFTWARE  
Integrating Constructor

<b>CRI Number</b>	MEP-G-001	<b>Trades</b>	ELEC	<b>Severity</b>	Low
<b>Description</b>	FF/E Lighting Fixture floor plan symbol shorter than the fixture given dimensions in the online specification. According to specification fixture dimensions are 1265mm x 108mm x 100mm.				
<b>Floor</b>	Level 8	<b>Grid Ref.</b>	B-C/7-8	<b>Sheet Ref.</b>	E-32
<b>Modeling Assumption</b>	Modeled light fixture according to online specification.				
<b>Design Team Comments</b>	Correct, symbol used is standard Bestec symbol. Fixture dimensions stated are correct. [BESTEC]				
<b>Vico Comments</b>	Issue was resolved according to confirmed assumption. No need to update the model.			<b>Issue Status</b>	Resolved

Contractor is responsible for verification of all information before work installation is started.  
Copyright (c) 2012 by Vico Software, all rights reserved.

# BIM – UniSA Jeffrey Smart Building

## Constructability report example – contradiction between disciplines

HINDMARSH

VICO SOFTWARE  
Integrating Constructors

CRI Number	MEP-A-210	Trades	ARCH, MECH	Severity	Low
Description	Contradiction between architectural reflected ceiling plan(A2070) and mechanical floor plan(M-11). The position of the diffusers are not same on the two plan at gridline D-E/1-3.				
Floor	Level 7	Grid Ref.	D-E/1-3	Sheet Ref.	A2070 (CD03); M-11
Modeling Assumption	The diffusers were modeled according to the mechanical floor plan(M-11)(marked with blue)				
Design Team Comments	Waiting for response.				
Vico Comments	Issue is still open. Design team needs to provide updated Architectural and Mechanical floor plans. Issue can be fixed, if these diffusers are on the same place on the floor plans.			Issue Status	Pending


Contractor is responsible for verification of all information before work installation is started.  
Copyright (c) 2012 by Vico Software, all rights reserved.

# BIM – UniSA Jeffrey Smart Building

## Jeffrey Smart Building

### Stage 2 BIM – Services Coordination and Clash Detection


- Hindmarsh led the services team developing the shop model
- Weekly workshops held until all clashes resolved, mainly in plantrooms



# BIM – UniSA Jeffrey Smart Building


## Jeffrey Smart Building - OUTCOMES

- No variations for rework associated with services coordination.
- Reduced RFI / Site Instruction / Variation process and disruption
- Budget savings
- IMPROVED RELATIONSHIPS
- As-Built model available for future FM use
- Very positive student response
- Learning and teaching opportunity
- Value for money – below 0.2% contract value



# BIM – UniSA Jeffrey Smart Building

## Jeffrey Smart Building




# BIM – Ergo Apartments

## ERGO Apartments

Hindmarsh Apartment Development - Adelaide

Design & Construct Contract

5D – Quantities for Costs



The screenshot displays a BIM software interface with a 3D model of a multi-story apartment building on the left and a data table on the right. The table lists various construction items with their quantities, descriptions, units, and values. The item 'Bored Pile Under Ream\_WG-8P1' is highlighted in yellow.

Code	Description	Unit	Type
494	Wall Cabinet - Filler (M)-520mm 2		(1)
495	End panel4-End panel		(1)
496	End panel5-End panel		(1)
497	Sink - Kitchen (7)-780 x 500mm-358-Revit		(1)
498	Sink - Kitchen (7)-780 x 500mm-364-Revit		(1)
499	Sink - Kitchen (7)-780 x 500mm-365-Revit		(1)
500	Sink - Kitchen (7)-780 x 500mm-368-Revit		(1)
501	Sink - Kitchen (7)-780 x 500mm-369-Revit		(1)
502	Concrete-Rectangular-Column-390 SQ BLOCKWORK PIER		(1)
503	STAIR A PART 3-STAIR A PART 1		(1)
504	Floor-100 THk. Raft Slab		(1)
505	Concrete Beam_WG-M5 -900(5) x 900(w)		(2)
506	Rebar Bar-N 16 - Shape L		(0)
507	Rebar Bar-N 12 - Shape S		(0)
508	Rebar Bar-N 16 - Shape S		(0)
509	Rebar Bar-N 12 - Shape L		(0)
510	Rebar Bar-N 8 - Shape HT		(0)
511	Rebar Bar-N 10 - Shape L		(0)
512	Rebar Bar-N 10 - Shape HT		(0)
513	Rebar Bar-N20 - Shape S		(0)
514	Basic Wall-Precast Panel 175mm		(22)
515	Bored Pile Under Ream_WG-8P1		(59)
516	Bored Pile Under Ream_WG-8P3		(24)
517	Pad Footing_WG-P1		(3)
518	Bored Pile_WG-8P2		(52)
519	Bored Pile_WG-8P4		(4)
520	Bored Pile_WG-8P5		(12)
521	Bored Pile Under Ream_WG-8P6		(5)

# BIM – Ergo Apartments

## ERGO Apartments





# BIM – Lessons

## BIM – Lessons Learned

- Technology is only part of the story
- Having the right team is key (positive culture)
- Early contractor involvement is important - Integrated delivery model
- Concise BIM Management Plan / Model Progression Specification required – to be agreed with all parties at the outset
- Monitoring of model development important (outputs at the agreed time and to the required quality)
- Win/Win outcome results in increased acceptance

# BIM – Challenges

## BIM – Challenges

- **Creating a trusting and motivating team environment from the outset (Client best placed to select the team)**
- **Project Delivery system that supports excellent project delivery**
- **Resistance to change – “That’s the way we’ve always done it.”**
- **Internal acceptance of BIM in an organisation and strategic approach to implementation are critical**
- **Change to skill set of staff – Training & introduction of new or advanced roles (BIM Manager, Design Manager, PM, Project Engineer etc.)**
- **Perceived cost premium**
- **Perceived risks (Changed process)**
- **Staff/team capabilities need to be developed – no “off the shelf” solutions – Add BIM process to existing knowledge set**
- **Lack of BIM capable subcontractors – Mandating, Support & Training**

## Questions?

